BRUHATH BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work : UGD Maintanance in Sidedahalli Village Limit in Ward No.14, Bagalagunte

Sl. No	Description	Unit	Qty	Rates	
				In Figs	In Words
1	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specification	Cum	1264.27	299.98	Rupees two hundred ninety nine and ninety eight paise only
2	Providing and laying in position to required level or slopem 300mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, tsting of pipes and joints, including cost of materials, labour charges complete as per specifications.	Mtr	890.00	661.44	Rupees six hundred sixty one and forty four paise only
3	Constructing brick masonry circular type manhole 0.91m internal dia at bottom 0.91m deep and 0.56m dia at top with table moulded non-modular bricks of 50class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating cost of neat cement, foundation concrete M 10 mix using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 mix with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diametre confirming IS:12592, total weight cover and frame to be not less than 182kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complet as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately	Nos	37.00	14391.62	Rupees fourteen thousand, three hundred ninety one and sixty two paise only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57.

Executive Engineer
Dasarahalli Division

Sl. No	Description	Unit	Qty	Rates	
				In Figs	In Words
4	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0 Newton per sqmm (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Cum	18.45	7086.10	Rupees seven thousand, eighty six and ten paise only
5	Providing 20mm thick cement plaster in single coat with cement mortar 1:4 to stone masonry & concrete surface including rounding off corner wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	144.30	248.04	Rupees two hundred forty eight and zero four paise only
6	Providing and Fixing SFRC cover and Frame 560m (ID) Heavy duty Materials code No.0331	Each	66.00	954.00	Rupees nine hundred fifty four paise only
7	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications allow 60% of rate considered under item	Cum	1264.27	80.56	Rupees eighty and fifty six paise only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER - 8
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57.

Signature of the Contractor

Executive Engineer
Dasarahalli Division